

Introduction

- GSI BMPs
- Hydrologic Modeling
- Modeling Example
- Hydrostats Example
- Pre-sized Method & Calculator

Alice Lancaster, PE
Herrera Environmental Consultants
alancaster@herrerainc.com
phone: 206-441-9080


November 24, 2009

Herrera Environmental Consultants, Inc.



GSI BMPs

Mimic Pre-development Hydrologic Processes




Herrera Environmental Consultants, Inc.



GSI BMPs

Post Construction Soil Quality and Depth




Herrera Environmental Consultants, Inc.



GSI BMPs

Retained and Planted Trees




Herrera Environmental Consultants, Inc.



GSI BMPs

Dispersion Downspout & Sheet flow




Herrera Environmental Consultants, Inc.









GSI BMPs

Bioretention



Herrera Environmental Consultants, Inc.





GSI BMPs

Traditional Infiltration BMPs



Herrera Environmental Consultants, Inc.



Capability of GSI BMPs

BMP	Flow Control	Treatment *
Soil Amendment		required
Trees	X	
Dispersion	X	
Bioretention	X	X
Rainwater Harvesting	X	
Permeable Pavement	X	X
Green Roofs	X	
Bioretention (w/ underdrains)	X (peak)	X

* Infiltrating through soil meeting Ecology treatment requirements

Herrera Environmental Consultants, Inc.



Seattle Standards

- GSI required to MEF → Under Development
- Pre-developed Pasture
 - Match durations/flows to pasture condition ($1/2$ 2-yr to 2-yr)
- Pre-developed Forest
 - Match durations/flows to forest condition ($1/2$ 2-yr to 50-yr)
- Peak Flow Control
 - Maximum 2- and 25-year flows
- Water Quality Treatment (Infiltration BMPs)
 - Infiltrate 91 % through soil meeting treatment requirements

BASED ON CONTINUOUS MODELING


Herrera Environmental Consultants, Inc.



Pasture Duration Std

Match **post development** flows & durations from $1/2$ 2-year to 2-year to **pre-developed** pasture condition


Flow Duration Plot



Herrera Environmental Consultants, Inc.



Hydrologic Modeling




Herrera Environmental Consultants, Inc.



Single-Event Methods

- Single storm event (typically 24-hours)
- Simulate corresponding runoff (peak flow)
- Ex. SCS, SBUH, StormShed, xp-SWMM, HEC-HMS




Herrera Environmental Consultants, Inc.



Continuous Models

- Long-term input rainfall and evaporation
- Simulate long-term runoff, peak flows, and duration
- Ex. HSPF, WWHM, MGS Flood




Herrera Environmental Consultants, Inc.



Continuous Models

- Available Models
 - Western WA Hydrology Model (WWHM)
 - MGS Flood (Based on HSPF)
- HydroStats
- Pre-Sized Method



Herrera Environmental Consultants, Inc.



Model Status

Issue	WWHM3Pro	MGSFlood
Cost	Free	~\$1,500
158-year Prec/Evap	Import	Built-In
Bioretention Module	Complete	by Jan 2010
Permeable Pvmnt Module	Use Trench	by Jan 2010
Green Roof Module	Complete	by Jan 2010
Flow Frequency Correct for Infiltration BMPs	No	Yes

Herrera Environmental Consultants, Inc.



Model Inputs


- Rainfall Record (5-min)
- Evaporation Record (daily)
- Impervious Area(s)
 - Slope
- Pervious Area(s)
 - Vegetation
 - Soil type (A, B, C/D)
 - Slope
- BMP Configurations
 - Routing (stage-storage-discharge table)

Herrera Environmental Consultants, Inc.



Seattle Requirements

- Rainfall / Evaporation Record: MGS 158-year extended series
- 5 minute time step
- HydroStats Post Processor
- Modeling methods for BMPs in DR



Herrera Environmental Consultants, Inc.



Bioretention Model Example

- Site in Seattle
- 5 minute time-step
- Soil is Till (0.5 inch/hour design infilt. rate)
- Bioretention cell (12" ponding, no underdrain)
- Receiving runoff from 5,000 sf of imp. area
- Size area to achieve pasture standard
- Using bioretention module in WWHM3Pro

Herrera Environmental Consultants, Inc.



Modeling Requirements

Variable	Assumption
Precipitation Series	Seattle 158-year, 5-minute series.
Time Step	5-minutes.
Inflows to Facility	Surface flow and interflow from drainage area routed to facility.
Precipitation and Evaporation Applied	Yes. If model does not apply precipitation and evaporation to facility, include the facility area in the basin area (note that this will significantly underestimate the evaporation of ponded water).
Bioretention Soil Infiltration Rate	For imported City of Seattle bioretention soil per specification 7-21 see Table 4.13. For compost amended native soil, rate shall be equal to the native soil design infiltration rate.
Bioretention Soil Porosity	For imported City of Seattle bioretention soil per specification 7-21, porosity is 40 percent. For compost amended native soil, porosity can be assumed to be 30 percent.
Bioretention Soil Depth	Minimum of 12 inches for flow control. Minimum of 18 inches for water quality treatment.
Native Soil Design Infiltration Rate	Measured infiltration rate with correction factor applied. If applicable (Section 4.3.3, Appendix E). If imported bioretention soil is used, a correction factor for plugging is not required.
Infiltration Across Wetted Surface Area	Yes if side slopes are 3H:1V or flatter. For steeper side slopes, only infiltration across the bottom area is modeled.
Underdrain (optional)	If underdrain is placed at bottom extent of the bioretention soil layer, all water which enters the facility must be routed through the underdrain. If there is no liner or impermeable layer and the underdrain is elevated within the bioretention soil, water stored in the bioretention soil below the underdrain may be allowed to infiltrate.
Outlet Structure	Overflow elevation set at maximum ponding elevation (excluding freeboard). May be modeled as weir flow over riser edge or notch. Note that total facility depth (including freeboard) must be sufficient to allow water surface elevation to rise above the overflow elevation to provide head for discharge.

Herrera Environmental Consultants, Inc.

Bioret. Representation

Herrera Environmental Consultants, Inc.

Model Configuration

Herrera Environmental Consultants, Inc.

WWHM Example

Load Precipitation/Evaporation Series

Herrera Environmental Consultants, Inc.

WWHM Example

Load Precipitation/Evaporation Series

Load Alternate Precip

Herrera Environmental Consultants, Inc.

WWHM Example

Load Precipitation/Evaporation Series

Analysis

Herrera Environmental Consultants, Inc.

Seattle GSI BMPs & Hydrologic Modeling- A Lancaster, Herrera

WWHM Example

Select 5 minute Time Step and Duration Range

Select "Options" in View Menu

Herrera Environmental Consultants, Inc.

WWHM Example

Predeveloped Basin → Select area, soil type, land cover and slope

Herrera Environmental Consultants, Inc.

WWHM Example

Developed Mitigated Basin → Impervious with same area and slope

Herrera Environmental Consultants, Inc.

WWHM Example

Developed Mitigated Basin → Route to BMP

Herrera Environmental Consultants, Inc.

WWHM Example

Duration Curve Results (iterative sizing)

Bioretention bottom area= 260 sf (5.2% of contributing impervious area)







Herrera Environmental Consultants, Inc.

WWHM Example

Flow Frequency Results


Export and Evaluate in Hydrostats

Herrera Environmental Consultants, Inc.



Hydrostats

Compliance Statistics




Herrera Environmental Consultants, Inc.



Hydrostats

Compliance Statistics




Herrera Environmental Consultants, Inc.



Hydrostats

Report



Herrera Environmental Consultants, Inc.



Troubleshooting


- WWHM Bioretention → "Freeboard"= ponding
- WWHM Bioretention → Takes 80 min to run
- WWHM Permeable Pymnt Facilities → Use ave. subsurface ponding depth as aggregate depth
- WWHM Flood Frequency (peak flows) → Incorrect for infiltration facilities (use Hydrostats)
- Pre-sized BMPs sized using preliminary shorter precip series → with 158-yr series, pre-sized infiltration BMPs are somewhat conservative and detention BMPs sized for peak are smaller

Herrera Environmental Consultants, Inc.



BMP Performance

Infiltration BMPs



Draft Sizing Factors


Herrera Environmental Consultants, Inc.



BMP Performance

Detention BMPs

Cannot achieve pasture or forest duration standard for smaller areas with minimum 0.5 inch orifice



Note: 7,000 sf minimum for pasture standard with 0.25 inch orifice


Herrera Environmental Consultants, Inc.



BMP Performance

Detention BMPs

- Maximize flow control benefit:
Size 0.5" orifice and a 3-foot live storage depth for no overflows during the 158-year period



Herrera Environmental Consultants, Inc.



Simplified Sizing Tool

- Small sites: <10,000 sf impervious area
- Pasture and Peak Stds
- Pre-designed BMPs
- Flow credits
 - Impervious reduction credit
- Sizing equations
 - BMP Size = f (Impervious Area & infiltration rate)
- Site design & BMP sizing without continuous modeling

BMP	Design Infiltr. Rate (in/hr)	Sizing Factor
Bioretention Cell		
2 inch ponding depth	0.25	23.0%
	0.5	15.8%
	1.0	9.3%
6 inch ponding depth	0.25	14.6%
	0.5	9.9%
	1.0	6.4%
12 inch ponding depth	0.25	8.9%
	0.5	6.5%
	1.0	4.1%


Herrera Environmental Consultants, Inc.



Flow Control Credits



- Impervious surface reduction credit
- Degree standard achieved



Seattle Public Utilities

Herrera Environmental Consultants, Inc.



Flow Control Credit BMPs

- Retained Trees
- Newly Planted Trees
- Green Roof
- Dispersion
- Permeable Pavement Surface

Herrera Environmental Consultants, Inc.



Flow Control Credit Design

- Retained Trees
- Newly Planted Trees
- Green Roof
- Dispersion
- Permeable Pavement Surface

- Evergreen and deciduous trees
- Minimum 6" DBH

Literature review of infiltration, evapotranspiration, interception

Herrera Environmental Consultants, Inc.



Flow Control Credit Design

- Retained Trees
- Newly Planted Trees
- Green Roof
- Dispersion
- Permeable Pavement Surface

- 4" single-course
- 4" multi-course
- 8" multi-course

Performance modeled (EcoRoof)

Herrera Environmental Consultants, Inc.



Flow Control Credits

Facility Type	Design Variable	Flow Control Credit	
		Pasture Standard	Peak Standard
Retained Trees	Evergreen	20% canopy area (min 100 sf/tree)	
	Deciduous	10% canopy area (min 50 sf/tree)	
New Trees	Evergreen	50 sf / tree	
	Deciduous	20 sf / tree	
Green Roof	4 inch depth	46%	71%
	8 inch depth	54%	79%
Dispersion	NA	90%	100%
Permeable Pavement Surface (3" subbase)	Slope ≤ 2%	100%	100%
	Slope 2% - 5%	45%	70%

Herrera Environmental Consultants, Inc.



Flow Control Credits

Facility Type	Design Variable	Flow Control Credit	
		Pasture Standard	Peak Standard
Retained Trees	Evergreen	20% canopy area (min 100 sf/tree)	
	Deciduous	10% canopy area (min 50 sf/tree)	
New Trees	Evergreen	50 sf / tree	
	Deciduous	20 sf / tree	
Green Roof	4 inch depth	46%	71%
	8 inch depth	54%	79%
Dispersion	NA	90%	100%
Permeable Pavement Surface (3' subbase)	Slope ≤ 2%	100%	100%
	Slope 2% - 5%	45%	70%

Herrera Environmental Consultants, Inc.



Flow Control Credits

Facility Type	Design Variable	Flow Control Credit	
		Pasture Standard	Peak Standard
Retained Trees	Evergreen	20% canopy area (min 100 sf/tree)	
	Deciduous	10% canopy area (min 50 sf/tree)	
New Trees	Evergreen	50 sf / tree	
	Deciduous	20 sf / tree	
Green Roof	4 inch depth	46%	71%
	8 inch depth	54%	79%
Dispersion	NA	90%	100%
Permeable Pavement Surface (3" subbase)	Slope ≤ 2%	100%	100%
	Slope 2% - 5%	45%	70%

Herrera Environmental Consultants, Inc.



Flow Control Credits

Facility Type	Design Variable	Flow Control Credit	
		Pasture Standard	Peak Standard
Retained Trees	Evergreen	20% canopy area (min 100 sf/tree)	
	Deciduous	10% canopy area (min 50 sf/tree)	
New Trees	Evergreen	50 sf / tree	
	Deciduous	20 sf / tree	
Green Roof	4 inch depth	46%	71%
	8 inch depth	54%	79%
Dispersion	NA	90%	100%
Permeable Pavement Surface (3" subbase)	Slope ≤ 2%	100%	100%
	Slope 2% - 5%	45%	70%

Herrera Environmental Consultants, Inc.



Flow Control Credits


Facility Type	Design Variable	Flow Control Credit	
		Pasture Standard	Peak Standard
Retained Trees	Evergreen	20% canopy area (min 100 sf/tree)	
	Deciduous	10% canopy area (min 50 sf/tree)	
New Trees	Evergreen	50 sf / tree	
	Deciduous	20 sf / tree	
Green Roof	4 inch depth	46%	71%
	8 inch depth	54%	79%
Dispersion	NA	90%	100%
Permeable Pavement Surface (3" subbase)	Slope ≤ 2%	100%	100%
	Slope 2% - 5%	45%	70%

Impervious Area Mitigated = Green Roof Area x 71%
Downstream BMP Sized for Green Roof Area x 29%

Herrera Environmental Consultants, Inc.



Sizing Factors



- Infiltration BMPs
- Sized to achieve FC & WQ stds
- Function of contributing area and infiltration rate

Herrera Environmental Consultants, Inc.



Sizing Factor BMPs

- Bioretention Cell
- Permeable Pavement Facility
- Bioretention Planter
- Infiltration Trench
- Drywell

Herrera Environmental Consultants, Inc.



Sizing Factor Design

- Bioretention Cell
- Permeable Pavement Facility
- Bioretention Planter
- Infiltration Trench
- Drywell

–No underdrain
 –Ponding: 2, 6 or 12"
 –Side slopes 3H:1V
 –12" bioretention soil (18" for treatment) per Seattle specs

Herrera Environmental Consultants, Inc.



Sizing Factor Design

- Bioretention Cell
- Permeable Pavement Facility
- Bioretention Planter
- Infiltration Trench
- Drywell

–Aggregate depth: 1.5 or 3'

Herrera Environmental Consultants, Inc.




Sizing Factor Development

- Continuous Modeling Methods
 - WWHM3Pro
 - Glacial Till (hydrologic group C)/Mod. Slope
 - 5 minute time step
 - Contributing Imp Area: 2,000 – 10,000 sf
 - Design Infiltr. Rates: 0.25, 0.5 and 1.0 in/hr
- Developed Relationship
 - Contributing Imp Area and BMP Area
 - Linear, typical $R^2 \sim 0.99$

Herrera Environmental Consultants, Inc.




Sizing Factor Development



Herrera Environmental Consultants, Inc.




Sizing Factor Development



Herrera Environmental Consultants, Inc.




Sizing Factor Development



Herrera Environmental Consultants, Inc.



Sizing Factor Development



Herrera Environmental Consultants, Inc.



Sizing Factors- Bioretention

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Bioretention Cell				
2 inch ponding depth	0.25	23.0%	--	--
	0.5	15.8%	--	--
	1.0	9.3%	--	--
6 inch ponding depth	0.25	14.6%	33.1%	5.0%
	0.5	9.9%	20.5%	2.9%
	1.0	6.4%	10.6%	1.6%
12 inch ponding depth	0.25	8.9%	19.3%	3.0%
	0.5	6.5%	13.4%	1.7%
	1.0	4.1%	6.7%	0.9%

Herrera Environmental Consultants, Inc.



Sizing Factors- Bioretention

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Bioretention Cell				
2 inch ponding depth	0.25	23.0%	--	--
	0.5	15.8%	--	--
	1.0	9.3%	--	--
6 inch ponding depth	0.25	14.6%	33.1%	5.0%
	0.5	9.9%	20.5%	2.9%
	1.0	6.4%	10.6%	1.6%
12 inch ponding depth	0.25	8.9%	19.3%	3.0%
	0.5	6.5%	13.4%	1.7%
	1.0	4.1%	6.7%	0.9%

Herrera Environmental Consultants, Inc.



Sizing Factors- Bioretention

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Bioretention Cell				
2 inch ponding depth	0.25	23.0%	--	--
	0.5	15.8%	--	--
	1.0	9.3%	--	--
6 inch ponding depth	0.25	14.6%	33.1%	5.0%
	0.5	9.9%	20.5%	2.9%
	1.0	6.4%	10.6%	1.6%
12 inch ponding depth	0.25	8.9%	19.3%	3.0%
	0.5	6.5%	13.4%	1.7%
	1.0	4.1%	6.7%	0.9%

Bioretention Bottom Area = Contributing Impervious Area x 8.9%

Herrera Environmental Consultants, Inc.



Sizing Factors- Bioretention

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Bioretention Cell				
2 inch ponding depth	0.25	23.0%	--	--
	0.5	15.8%	--	--
	1.0	9.3%	--	--
6 inch ponding depth	0.25	14.6%	33.1%	5.0%
	0.5	9.9%	20.5%	2.9%
	1.0	6.4%	10.6%	1.6%
12 inch ponding depth	0.25	8.9%	19.3%	3.0%
	0.5	6.5%	13.4%	1.7%
	1.0	4.1%	6.7%	0.9%

Bioretention Bottom Area = Contributing Impervious Area x 3.0%

Herrera Environmental Consultants, Inc.



Sizing Factors- PP Facilities

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Permeable Pavement Facility				
6 inch ponding depth	0.25	60.6%	131.4%	--
	0.5	34.5%	52.4%	--
	1.0	33.3%	33.3%	--
12 inch ponding depth	0.25	38.2%	75.8%	--
	0.5	33.3%	38.7%	--
	1.0	33.3%	33.3%	--
Bioretention Planter with Underdrain				
6 inch ponding	NA	NA	NA	2.6%
12 inch ponding	NA	NA	6.5%	2.0%

Herrera Environmental Consultants, Inc.



Sizing Factors- PP Facilities

BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Permeable Pavement Facility				
6 inch ponding depth	0.25	60.6%	131.4%	--
	0.5	34.5%	52.4%	--
	1.0	33.3%	33.3%	--
12 inch ponding depth	0.25	38.2%	75.8%	--
	0.5	33.3%	38.7%	--
	1.0	33.3%	33.3%	--
Bioretention Planter with Underdrain				
6 inch ponding	NA	NA	NA	2.6%
12 inch ponding	NA	NA	6.5%	2.0%

Pavement Area = Contributing Impervious Area x 38.7%

Herrera Environmental Consultants, Inc.



Sizing Factors- Tradtl. Infiltration


BMP	Design Infiltr. Rate (in/hr)	Pasture Standard	Peak Standard	Treatment Standard
Infiltration Trench				
1.5 foot depth	0.25	27.3%	55.1%	12.7%
	0.5	16.8%	30.0%	8.3%
	1.0	10.7%	17.4%	5.3%
3.0 foot depth	0.25	17.0%	31.9%	8.6%
	0.5	12.0%	20.1%	5.9%
	1.0	7.8%	13.1%	4.0%
Dry Well				
4 foot depth	0.25	13.6%	24.9%	7.5%
	0.5	10.1%	17.6%	5.1%
	1.0	6.7%	11.1%	3.5%
6 foot depth	0.25	9.7%	17.5%	6.1%
	0.5	7.9%	13.2%	4.2%
	1.0	5.7%	8.9%	2.8%

Herrera Environmental Consultants, Inc.



Sizing Factors- Tradtl. Detention

BMP	Contributing Area	Pasture Standard	Peak Standard
Detention Pipe			
24 inch diameter	< 5,000 sf	0.0000263A^1.9	0.00000508A^2.10
	5,000 – 10,000 sf	0.120A – 235	0.123A – 314
36 inch diameter	< 5,000 sf	0.000000219A^2.40	0.00000277A^2.05
	5,000 – 10,000 sf	0.0515A – 110	0.0546A – 167



Herrera Environmental Consultants, Inc.



Sizing Calculator

- Guides designer through selecting and sizing BMPs
- Documentation for project submittal
- Includes MEF calculations

Herrera Environmental Consultants, Inc.

